

**ACKNOWLEDGEMENT
RECEIPT OF ADDENDUM #1
BID #16-151-3
SHAKERAG PARK WILDLIFE
VIEWING DECK**

Upon receipt of documents, please fax or mail this page to:

***City of Johns Creek– Purchasing Division
Attention: John T. Henderson, Purchasing Manager
12000 Findley Rd., Suite-400
Johns Creek, GA 30097
Phone: 678-512-3233
Fax: 678-512-3244
Email: john.henderson@johnscreekga.gov***

I hereby acknowledge receipt of documents pertaining to the above referenced bid/RFP.

COMPANY NAME: _____

CONTACT PERSON: _____

ADDRESS: _____

CITY: _____ ***STATE:*** _____ ***ZIP:*** _____

PHONE: _____ ***FAX:*** _____

EMAIL ADDRESS: _____

Signature

Date

Purchasing Division

**Warren Hutmacher
City Manager**

**Michael E. Bodker
Mayor**

ADDENDUM NUMBER 1
BID #16-151-3
SHAKERAG PARK WILDLIFE VIEWING DECK

To All Prospective Vendors:

To follow is Addendum Number 1 on the Invitation to Bid for the Shakerag Park Wildlife Viewing Deck Project. Please be sure to fax back the "Acknowledgement of Receipt of Addendum #1 as soon as possible.

Opening comments:

This is a federally funded project by a CDBG grant which includes the pertinent Davis-Bacon wage rate documentation. The deck is approximately 30' x 40' constructed with #1 yellow pine or composite material (Trex). Seating and hand railing will be pressure treated #1 yellow pine. All decking will be constructed of a composite material. Support posts will be 6' x 6' pressure treated material. Concrete deck footings will be installed and rated at 3000 psi. All connection bolts will be galvanized steel with washers. Elevation will be determined in the field in the pre-construction meeting and stain will be determined at a later date. Deck must meet all ADA requirements.

Questions from pre-bid conference held on May 9, 2016:

1. Will the contractor be required to submit plans and obtain City permits?

Answer: Yes. Contractor must obtain all permits required from the city; however, there will be no charge for the permits.

2. Which direction is the deck going?

Answer: Start at the edge area and work back and then tie in to the sidewalk which the sidewalk contractor will be responsible for. A rectangular structure going straight back.

3. The access points are going to be so big. Are you going to make contractor do that on this project?

Answer: All access points must comply with ADA standards

4. With the trail going through, wouldn't there need to be an opening on both sides?

Answer: Yes

5. Is there a height requirement?

Answer: To be determined with successful contractor at a later date.